BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineer
Yelahanka Division
B.B.M.P. Bengaluru - 64

APPROVED TENDER SCHEDULE –'B'

Name of Work: -Reconstruction of masonry storm water drain and covering slab in GKVK layout to Allalasandra in ward No:84

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
1	Dismantling size stone masonry in clay mortor and stacking the size stone within aradions of 50m and removing the debries to a distance up to 200m etc as per specifications and directions of the engineer in charge of the work	Cum	117.00	75.60	Rupess seventy five and paise sixty only
2	KSRRB 300-1.Earth work excavatinn by manual means in ordinary soil invlving an average horizontal throw up to 2 meters and an average lift uo to 1.5m,exnavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications (Item no19.1,Page no 138, PWD SR 2014-15)	Cum	763.38	75.60	Rupess seventy five and paise sixty only
3	KSRB 4-1.3:Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180kgs, with 40mm and down size graded granite metal course aggregates @0.85cum and fine aggregates @0.57cum machine mixed,machine mixed,concrete laid in layers not exceeding 15cms.thick, well compacted in foundation,including cost of all materials,labour,HOM of machinery,curing complete as per specifications.Specification no KDS4.1.4.2(Item no4.3,Page no12.PWD SR 2014-15)	Cum	83.12	4847.04	Rupess four thousand eight hundred forty seven and paise four only
4	KSRRB 4.1:6Providing and laying in position plain cement concrete mix 1:2:4 with cement @240kgs, with 20mm and down size graded granite metal coarse aggregates @0.69 cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15cms thick well compacted.in foundation.plinth and cills.including cost of all materials, labour, HOM of machineries, curing complete as per specifications. Specification no 4.1.4.2 **(Page.12 & Item No. 4.6)**	Cum	65.74	5327.64	Rupess five thousand three hundred twenty seven and paise sixty four only
5	KSRB 5.3-3 : Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stone chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specification. KBS 5.1.13 (P.23/5.9) PWD SR 2014-15	Cum	414.72	4542.48	Rupess four thousand five hundred forty two and paise forty eight only
			11700.00	10.00	Rupess ten only

BRUHATH BENGALURU MAHANAGARA PALIKE
Yelahanka Division, Yelahanka Zone

Executive Engineer
Yelahanka Division
B.B.M.P. Bengaluru - 64

APPROVED TENDER SCHEDULE –'B'

Name of Work: -Reconstruction of masonry storm water drain and covering slab in GKVK layout to Allalasandra in ward No:04

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
1	Dismantling size stone masonry in clay mortor and stacking the size stone within aradious of 50m and removing the debries to a distance up to 200m etc as per specifications and directions of the engineer in charge of the work	Cum	117.00	75.60	Rupess seventy five and paise sixty only
2	KSRRB 300-1.Earth work excavatinn by manual means in ordinary soil invlving an average horizontal throw up to 2 meters and an average lift up to 1.5m,excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications (Item no19.1,Page no 138, PWD SR 2014-15)	Cum	763.38	75.60	Rupess seventy five and paise sixty only
3	KSRB 4-1.3:Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed,machine mixed,concrete laid in layers not exceeding 15cms.thick, well compacted in foundation,including cost of all materials,labour,HOM of machinery,curing complete as per specifications.Specification no KDS4.1.4.2(Item no4.3,Page no12.PWD SR 2014-15)	Cum	83.12	4847.04	Rupess four thousand eight hundred forty seven and paise four only
4	KSRRB 4.1:6Providing and laying in position plain **cement concrete mix 1:2:4** with cement @240kgs, with 20mm and down size graded granite metal coarse aggregates @0.69 cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15cms thick well compacted.in foundation,plinth and cills,including cost of all materials, labour, HOM of machineries, curing complete as per specifications. Specification no 4.1.4.2 **(Page.12 & Item No. 4.6)**	Cum	65.74	5327.64	Rupess five thousand three hundred twenty seven and paise sixty four only
5	KSRB 5.3-3 : Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stone chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specification. KBS 5.1.13 (P.23/5.9) PWD SR 2014-15	Cum	414.72	4542.48	Rupess four thousand five hundred forty two and paise forty eight only
			11700.00	10.00	Rupess ten only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Technical Manager (West) KRIDL, BBMP,	
				Rate	Rate in Words
6	KSRB 4.2.2 : Providing and laying in position Reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.460cum with super plasterise @ 3lts conforming etc as per specification&direction of the engineer incharge of work(pwd sr2014-15,p.no13,sno4.11)	Cum	77.96	6065.28	Rupess six thousand sixty five and paise twenty eight only
7	KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per specifications.Specification noKBS 4.6.3,TMT bars Fe550(pwd sr 2014-15,p.no17,s.no 4.46)	Qtl	93.55	7905.60	Rupess seven thousand nine hundred five and paise sixty only
8	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, attached pilasters,bittresses,buttresses plinth and string course including cost of all materials,labour complete asperspecification. Specification no.KBS 4.6.2 (pwd sr2014-15,p.no15/4.31)	Sqm	345.60	292.68	Rupess two hundred ninety two and paise sixty eight only
9	KSRB 15.1.3: Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining including cost of materials labour, curng complete as per specifications.	Sqm	691.20	92.88	Rupess ninety two and paise eighty eight only
10	KSRB M100-1 Loading and un loading of stone boulder/Stone aggregates/ sand/kanker/ Moorum, KSRB M100-1:Placing tipper at loading point,loading with front end loader,dumping,turning for return trip,excluding time for haulage and return trip complete as per specifications(Item no17.1,Page no 130, PWD SR 2014-15)	Cum	763.38	68.04	Rupess sixty eight and paise four only

Signature of the Contractor

Assistant Executive Engineer
Vidyarayanapura Sub-division
KRIDL, BBMP, Bangalore

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.